



TERRA MAKE MOBILE CONCRETE BATCHING PLANT

TFP SERIES

Technical Specification

Model	TFP 20	TFP 25	TFP 30	TFP 45
Output capacity	20 M ³ / Hr.	25 M ³ / Hr.	30 M ³ / Hr.	45 M ³ / Hr.
Plant Assembly	Whole plant assembly is on wheel mounted single chassis			
Mixer type	Pan type mixer/ Planetary mixer/ Twin Shaft mixer			
Main mixer drive	20 HP	25 HP	30 HP	40 HP
Material storage system	2 x 2 cross bin feeder			
Material storage capacity	12 M ³	12 M ³	14 M ³	20 M ³
Material weighing system	Digital load cell based weighing of aggregates, cement, water and additive			
Cement feeding system	Through inclined Screw conveyor			
Mobility arrangement	Provided along with tow bar facility			
Control panel	PLC based control panel with internal cabling			
Total connected power	45 HP	50 HP	58 HP	79 HP
Suggested DG Set	50 KVA	62 KVA	82 KVA	100 KVA
Concrete discharge height	2.1 Meter from the ground level			

Optional Accessories

- Scada software with computer
- Fly ash / GGBS feeding system
- Storage silos
- Prefab cabin for control panel