



TERRA MAKE MOBILE CONCRETE BATCHING PLANT

TMP SERIES

Technical Specification

Model	TMP 15	TMP 18	TMP 24	TMP 30
Output capacity	15 M ³ / Hr.	18 M ³ / Hr.	24 M ³ / Hr.	30 M ³ /Hr.
Plant assembly	Whole plant assembly on single chassis			
Mixer type	Turbo pan type mixer with spring backed arms			
Material storage capacity	10 M ³	10 M ³	12 M ³	12 M ³
Material weighing system	Digital load cell based weighing of Aggregates, cement, water separately			
Cement feeding system	Through inclined screw conveyor			
Mobility Arrangement	Provided along with tow bar facility			
Total connected power	30 HP	35 HP	40 HP	45 HP
Suggested D.G. set	40 KVA	40 KVA	50 KVA	62 KVA
Concrete discharge height	1 meter from Ground level			

Optional Accessories

- Scada software with computer
- Fly ash / GGBS feeding system
- Storage silos
- Prefab cabin for control panel