



**TERRA MAKE MOBILE CONCRETE BATCHING
PLANT WITH REVERSIBLE DRUM TYPE MIXER**

TRM SERIES

Technical Specification

Model	TRM 15	TRM 20	TRM 30
Output capacity	15 M ³ / Hr.	20 M ³ / Hr.	30 M ³ / Hr.
Material storage capacity	10 M ³	12 M ³	14 M ³
Mixing and Discharge system	Forward rotation of drum mixes the material and reverse rotation of drum discharges the concrete.		
Material weighing system	Digital load cell based weighing of aggregates		
Cement feeding system	Through inclined screw conveyor		
Water feeding system	Timer based accurate water feeding system		
Control panel	Fully automatic PLC based control panel		
Pneumatic wheels	2 nos	2 nos	4 nos
Water tank capacity	200 litres	250 litres	300 litres
Total connected power	25 HP	30 HP	43 HP
Suggested DG Set	40 KVA	50 KVA	62 KVA
Concrete discharge height	1.2 meter from GL	1.5 meter from GL	1.7 meter from GL



TRM - 30

Optional Accessories

- Prefab cabin for control panel
- Fly ash / GGBS feeding system
- Storage silos
- Scada software with computer